
# BENTLEY CROSSING STAGES 2 AND 3 AT WALKER ROAD, BENTLEY PARK FOR WALKER ROAD PTY LTD.

# **BENTLEY CROSSING STAGES 2 AND 3**



# LOCALITY PLAN

### DRAWING INDEX

DWG No.	TITLE
15495 - C201 15495 - C202	LOCALITY PLAN, DRAWING INDEX & TYPE SECTIONS DRAWING SET NOTES
15495 - C203	EARTHWORKS PLAN - SHEET 1 OF 2
15495 - C204	EARTHWORKS PLAN - SHEET 2 OF 2
15495 - C205	ROADWORKS AND DRAINAGE PLAN - SHEET 1 OF 2
15495 - C206	ROADWORKS AND DRAINAGE PLAN - SHEET 2 OF 2
15495 - C207	BENTLEY DRIVE LONGITUDINAL SECTION
15495 - C208	BENTLEY DRIVE CROSS SECTIONS
15495 - C209	ROAD 02 LONGITUDINAL SECTION
15495 - C210	ROAD 02 CROSS SECTIONS
15495 - C211	INTERSECTION AND CUL DE SAC SETOUT PLAN
15495 - C212	DRAINAGE CATCHMENT PLAN
15495 - C213	DRAINAGE LONGITUDINAL SECTIONS
15495 - C214	DRAINAGE CALCULATION TABLES
15495 - C215	EROSION AND SEDIMENT CONTROL PLAN
15495 - C216	SEWERAGE PLAN - SHEET 1 OF 2
15495 - C217	SEWERAGE PLAN - SHEET 2 OF 2
15495 - C218	SEWER LONGITUDINAL SECTIONS
15495 – C219	WATER RETICULATION AND LINEMARKING PLAN

### CROSS SECTION NOTES

REFER EARTHWORKS PLAN AND CROSS SECTION DRAWINGS FOR SIDE BATTER AND ALLOTMENT EARTHWORKS TREATMENT.

ALL KERB AND CHANNEL TYPES TO BE IN ACCORDANCE WITH FNQROC STANDARD DWG No. S1000

SINGLE TURF STRIP WITH RETURNS BEHIND ALL KERB AND CHANNEL. IN ACCORDANCE WITH DEVELOPMENT MANUAL.

T25mm TYPE 2.1 BASE COURSE (CBR 80) COMPACTED TO 100% SRDD, OVERLAYING 125mm TYPE 2.2 SUB-BASE COURSE (CBR 60) COMPACTED TO 98% SRDD (BENTLEY DRIVE).

100mm TYPE 2.2 BASE COURSE (CBR 60) COMPACTED TO 100% SRDD, OVERLAYING 100mm TYPE 2.3 SUB-BASE COURSE (CBR 45) COMPACTED TO 98% SRDD (ROAD 02).

SUB-GRADE TO BE TRIMMED AND COMPACTED TO 98% SRDD. SUB-GRADE CBR TO BE CHECKED AND SUBMITTED TO ENGINEER FOR CONFIRMATION OF PAVEMENT DESIGN AND APPROVALS BY CAIRNS CITY COUNCIL. REFER TO SUBGRADE AND FILL NOTES 13030-CO2

ASSUMED DESIGN SUBGRADE SOAKED CBR = 10 AT 98% SRDD.

ASPHALT SURFACE (30mm TYPICAL.)

PRIME COAT -C170 BITUMEN 8% CUT BACK 0.8 litres/sq.m.

ASPHALT 48 HOURS MIN. AFTER PRIME COAT


THE CONTRACTOR IS TO ENSURE THAT THE PAVEMENT COURSES ARE SET DOWN SUFFICIENTLY TO ALLOW FOR THE THICKNESS OF ASPHALT SURFACING.

VERGE (FOOTPATH) CROSSFALLS NOT TO EXCEED THOSE SPECIFIED.


ALL FOOTPATHS ARE TO BE HYDROMULCHED / GRASSED (DRILL SEEDED WITH APPROVED GRASS SPECIES), FERTILISED, AND MAINTAINED FOR THE REQUIRED MAINTENANCE PERIOD.

### SUBSOIL DRAINS:


FOR SUBSOIL DRAIN DETAILS REFER TO FNQROC STD DRG S1095.



TYPICAL SECTION - ROAD 02 CH 0.000 - 140.000 NTS



TYPICAL SECTION - BENTLEY DRIVE CH 71.920 - 105 NTS



TYPICAL SECTION - BENTLEY DRIVE

D	TITLEBLOCK REVISED	08.06.17
С	TYPICAL SECTIONS REVISED	26.05.17
В	15495 - C219 PLAN NAME CHANGED	12.05.16
Α	FOR COUNCIL SUBMISSION	15.02.16
ISSUE	DESCRIPTION	DATE

**FOR** CONSTRUCTION

rawing Status

SCALE N/A	Orig. Sneet	П
SCALE IN/A	A1	ı
DO NOT SCALE DRAV	VINGS	ı
Scales Before Reduction		ı
		ı
		ш

**JACOBS** 

WALKER ROAD PTY LTD

**CHERRYBROOK** STAGES 2 AND 3 LOCALITY PLAN - DRAWING **INDEX - TYPICAL CROSS SECTIONS** 

	Drawn JP	Designed PAM		erified JB	
ا ف	Approved RJC			Date JUN 2017	
	Drawing Nun			Revision D	

### CONCRETE NOTES

150mm THICK CONCRETE SLAB PAVEMENT (APPROVED FINISH). SL82 MIN FABRIC, 50mm TOP COVER. OVERLAYING - 150mm THICK CBR45 (MIN) TYPE 2.3, COMPACTED TO 98% SRDD.

### SUBGRADE AND FILL NOTES

AREA TO BE CLEARED AND GRUBBED OUT TO REMOVE TOPSOIL AND ORGANIC MATERIAL

WHERE NECESSARY APPROVED IMPORTED FILL TO BE SPREAD IN LAYERS NOT EXCEEDING 200mm AND COMPACTED USING VIBRATORY ROLLER TO 98% SRDD AT OPTIMUM MOISTURE CONTENT.

ANY TREES TO BE REMOVED SHALL BE EXCAVATED AND THE HOLE FILLED WITH APPROVED IMPORTED FILL COMPACTED AS ABOVE.

FILLING TO BE BROUGHT UP TO THE UNDERSIDE OF THE ROAD PAVEMENT AND TRIMMED TO THE DESIRED LEVELS.

APPROVED IMPORTED FILLING UNDER THE PAVEMENT TO HAVE A CBR OF 15 AND A MIN DEPTH OF 250mm. IMPORTED GRAVEL TYPE MUST COMPLY WITH ALL ASPECTS OF THE "MAIN ROADS STANDARD SPECIFICATION MRS 11.05 - UNBOUND PAVEMENTS".

ALL SOFT SPOTS SHALL BE EXCAVATED BACK TO FIRM GROUND. THE BASE OF THE EXCAVATION COMPACTED AND BACKFILLED WITH APPROVED IMPORTED FILL COMPACTED AS ABOVE.

ALL FILL SHALL BE TESTED FOR COMPACTION IN ACCORDANCE WITH AS.3798 AND FNQROC REQUIREMENTS.

SUB-GRADE TO BE TRIMMED AND COMPACTED TO 98% SRDD ( ASSUMED SOAKED CBR 7 MIN

NO PAVEMENT GRAVEL IS TO BE DELIVERED TO THE SITE UNTIL AFTER THE CONTRACTOR HAS RECEIVED WRITTEN CONFIRMATION OF THE PAVEMENT DESIGN FROM THE SUPERINTENDENT.

THE CONTRACTOR IS TO ENSURE THAT THE PAVEMENT COURSES ARE SET DOWN SUFFICIENTLY TO ALLOW FOR THE THICKNESS OF ASPHALT SEAL COAT.

### ASPHALT SURFACE (WHERE SPECIFIED)

THE PAVEMENT IS TO BE BROOMED CLEAN AND SHALL BE DRY PRIOR TO APPLYING PRIME COAT.

PRIME COAT SHALL BE APPLIED 48 HOURS PRIOR TO ASPHALT SEALING

APPLY 30mm (50mm IN SPECIFIED AREAS) OF APPROVED ASPHALT

THE PRIME COAT AND HOT MIX DESIGN SHALL BE SUPPLIED AND PLACED IN ACCORDANCE WITH COUNCIL DEVELOPMENT MANUAL REQUIREMENTS, WITH POLYMER ADDITIVES.

THE CONTRACTOR SHALL PROVIDE A TRAFFIC MANAGEMENT PLAN IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR APPROVAL BY COUNCIL PRIOR TO THE PRESTART MEETING.

- TRAFFIC CONTROL DEVICES (ROAD EDGE GUIDE POSTS, SIGNS, ETC) SHALL BE SUPPLIED AND INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE CURRENT ISSUE OF THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES AS ISSUED BY THE DEPARTMENT OF TRANSPORT, QUEENSLAND.
- REFER TO THE "TYPE CROSS SECTIONS" DRAWING FOR PAVEMENT DETAILS
- CONSTRUCTION AND INSTALLATION OF ALL WORKS AS DETAILED ON THIS DRAWING IS TO BE IN ACCORDANCE WITH THE PROCEDURES, SPECIFICATIONS AND DRAWINGS CONTAINED IN THE CURRENT ISSUE OF THE "REGIONAL DEVELOPMENT MANUAL" AS ISSUED BY FNQROC, AND TO THE REQUIREMENTS OF THE
- THE CONTRACTOR SHALL LIAISE WITH THE RELEVANT AUTHORITIES TO CONFIRM THE LOCATION OF ALL EXISTING SERVICES, AND SHALL ARRANGE FOR THE REMOVAL OR RELOCATION OF ANY SERVICES WHICH WILL BE AFFECTED BY THE WORKS.
- THE CONTRACTOR/BUILDER SHALL OBTAIN COUNCIL APPROVALS PRIOR TO COMMENCING ANY CONSTRUCTION WORKS EXTERNAL TO THE SITE.
- THE CONTRACTOR SHALL REMOVE ALL EXISTING CONSTRUCTION, TREES, SERVICES ETC AS NECESSARY TO PERMIT CONSTRUCTION OF THE NEW WORKS.
- THE CONTRACTOR SHALL OBTAIN COUNCIL INSPECTIONS AND THEIR WITNESS TO TESTING PRIOR TO MAKING SEWERS AND WATER MAINS LIVE. A COPY OF COUNCIL'S INSPECTION CERTIFICATE SHALL BE PROVIDED TO THE SUPERINTENDENT PRIOR TO PRACTICAL COMPLETION.
- THE CONTRACTOR SHALL PROVIDE "AS CONSTRUCTED" DRAWINGS PREPARED BY A REGISTERED SURVEYOR IN ACCORDANCE WITH FNOROC TO THE SUPERINTENDENT PRIOR TO PRACTICAL COMPLETION.
- ALL TREES ON THE SITE ARE TO REMAIN UNLESS NOTED OTHERWISE. PROTECTION OF EXISTING TREES SHALL BE IN ACCORDANCE WITH AS4970 -2009 -PROTECTION OF TREES ON DEVELOPMENT SITES.
- THE CONTRACTOR SHALL COMPLY WITH ALL CONDITIONS OF THE COUNCIL'S DECISION NOTICE/NEGOTIATED DECISION NOTICE ISSUED FOR THE PROJECT —COPIES ARE AVAILABLE ON REQUEST.
- SUBSOIL FLUSH POINTS TO BE IN ACCORDANCE WITH FNOROC DWG No. S1095. WHERE FLUSH POINTS OCCUR AT STORMWATER PITS, ENSURE FLUSHING POINT IS PROVIDED INSIDE THE PIT TO THE DETAILS SHOWN ON FNOROC DWG No. S1095.
- 12. CCTV INSPECTIONS ARE TO BE CONDUCTED FOR ALL STORMWATER PIPES FOR COUNCIL ASSESSMENT

### SURVEY & EXISTING SERVICES

- HORIZONTAL DATUM IS MGA
- 2. LEVEL DATUM IS AHD.
- REFER TO THE RPS SURVEYORS FOR THE CONFORMATION OF SURVEY STATION SETOUT DETAILS INCLUDING LEVELS AND DATUMS.
- 4. THE EXISTING SERVICES SHOWN ON THESE DRAWINGS ARE DERIVED FROM SURFACE SURVEY AND COUNCIL RECORDS AND MAY NOT REPRESENT THE EXISTING SERVICES PRESENT BELOW THE SURFACE.
- CONTRACTOR SHALL BE RESPONSIBLE TO LOCATE ALL EXISTING SERVICES PRIOR TO ANY
- ALL DAMAGE TO EXISTING SERVICES SHALL BE MADE GOOD TO THE SATISFACTION OF THE SUPERINTENDENT AND THE RELEVANT AUTHORITY, ALL AT THE CONTRACTORS EXPENSE. THE CONTRACTOR SHALL NOTIFY THE RELEVANT AUTHORITY IMMEDIATELY WHEN ANY DAMAGE OCCURS.
- THE LINE AND LEVEL OF EXISTING UNDERGROUND SERVICES SHALL BE DETERMINED BY THE CONTRACTOR AND THE ENGINEER SHALL BE NOTIFIED OF ANY POTENTIAL CLASHES WITH DESIGN STRUCTURES AND SERVICES PRIOR TO COMMENCING CONSTRUCTION.
- EXISTING OUTLET LEVELS OR CONNECTION LEVELS FOR ALL DESIGN STORMWATER AND SEWER SHALL BE CONFIRMED BY THE CONTRACTOR AND THE ENGINEER SHALL BE NOTIFIED OF ANY VARIATIONS PRIOR TO COMMENCING CONSTRUCTION.
- PRIOR TO THE COMMENCEMENT OF CONSTRUCTION THE CONTRACTOR IS TO ESTABLISH ON SITE THE EXACT POSITION OF ALL UNDERGROUND SERVICES IN THE PROPOSED WORKS AREA. METHODS FOR ACHIEVING THIS WILL INCLUDE BUT NOT BE LIMITED TO:
   CAREFUL EXAMINATION OF THE CONTRACT DRAWINGS.

   CONSULTATION WITH THE RELEVANT SERVICE AUTHORITIES.
- COMPREHENSIVELY SCANNING THE AFFECTED AREAS WITH A CABLE DETECTOR AND MARKING ON THE GROUND THE POSITION OF ALL SERVICES.
- HAND EXCAVATING TO EXPOSE ALL SUCH SERVICES WHICH MAY BE AFFECTED BY THE PROPOSED WORKS UNDER THE DIRECTION OF THE RELEVANT SERVICE AUTHORITY
- 10. THE CONTRACTOR IS TO BRING TO THE SUPERINTENDENT'S ATTENTION ANY DISCREPANCIES BETWEEN THE EXISTING SERVICES THUS IDENTIFIED AND DOCUMENTED SERVICES WHICH MIGHT AFFECT THE PROPOSED WORKS. APPROPRIATE MEASURES TO RESOLVE ANY CONFLICT WILL BE DOCUMENTED BY THE SUPERINTENDENT.

### SEWERAGE RETICULATION

- 1. ALL SEWER PIPES SHALL BE 150 DIA PVC, CLASS SEH, UNLESS NOTED OTHERWISE.
- 3. WHERE MANHOLES OCCUR AT THE ENDS OF SEWER LINES, THE HOUSE CONNECTION BRANCH (PCB) IS TO BE CONNECTED DIRECTLY TO MANHOLE TO AVOID DRY MANHOLE SITUATIONS. REFER TO PLAN FOR DEPLY TO SET TO
- 4. REFER TO THE SEWERAGE LONGITUDINAL SECTIONS FOR SEWER PIPE GRADES, INVERT LEVELS STORMWATER CLASHES, ETC.
- 5. CONSTRUCTION OF THE SEWERAGE RETICULATION SHALL BE IN ACCORDANCE WITH THE PROCEDURES, SPECIFICATIONS AND DRAWINGS INCLUDING REQUIREMENTS FOR "AS CONSTRUCTED" DRAWINGS AS CONTAINED INTHE CURRENT ISSUE OF THE "REGIONAL DEVELOPMENT MANUAL" AS ISSUED BY FNQROC, AND SHALL BE TO THE REQUIREMENTS OF THE COUNCIL.
- CONTRACTOR SHALL USE FIBREGLASS REINFORCED JUNCTIONS AT PCB's WHERE REQUIRED BY CAIRNS REGIONAL COUNCIL.
- INSTALL PIPE ANCHOR BLOCKS TO ALL 100 AND 150 DIA SEWERS AT GRADES GREATER THAN 1 ON 6 IN ACCORDANCE WITH FNQROCDWG No. S3015-CRC AND WSA.
- THE CONTRACTOR SHALL MAKE ALL APPLICATIONS AND PAY ALL FEES TO COUNCIL FOR THE SEWERAGE WORKS AND SHALL ARRANGE AND MANAGE COUNCIL'S INSPECTIONS AND TESTING OF THE WORKS. A COPY OF COUNCIL'S INSPECTION CERTIFICATE SHALL BE PROVIDED BY THE CONTRACTOR TO THE SUPER PRIOR TO PRACTICAL COMPLETION.
- 9. CCTV INSPECTIONS ARE TO BE CONDUCTED FOR ALL SEWERS FOR COUNCIL ASSESSMENT

### EARTHWORKS NOTES

- ALL FOOTPATHS SHALL BE GRASSED (DRILL SEEDED WITH APPROVED GRASS SPECIES) IN ACCORDANCE WITH LANDSCAPE SPECIFICATIONS, FERTILIZED AND MAINTAINED FOR THE REQUIRED MAINTENANCE
- ALL BARE EARTHWORKS AREAS (LOTS, DRAINS, PARKS, VERGES, ETC.), SHALL BE GRASSED (DRILL SEEDED WITH APPROVED GRASS SPECIES) FOR SLOPES UP TO AND INCLUDING 1 ON 4, OR HYDROMULCHED FOR SLOPES GREATER THAN 1 ON 4. USE APPROVED SEED MIX AND MAINTAIN, WATER AND FERTILISE FOR MAINTENANCE PERIOD.
- 3. CLEAR TREES, LARGE SHRUBS ETC FROM THE AREA OF LOTS AND ROAD RESERVES, ONLY FOR CONSTRUCTION OF ROADS AND SERVICES, AND EITHER REMOVE FROM SITE OR ALTERNATIVELY CHIP MULCH AND STOCKPILE FOR RE-USE IN LANDSCAPING. CONTRACTOR SHALL OBTAIN COUNCIL INSPECTION AND APPROVAL PRIOR TO COMMENCING ANY TREE AND VEGETATION CLEARING ALL VEGETATION/CONSERVATION ZONES SHALL BE RETAINED AND SHALL BE ADEQUATELY FENCED/SEGREGATED PRIOR TO COMMENCING CONSTRUCTION.
- SLASH THE EARTHWORKS AREA. RAKE AND STOCKPILE CUT VEGETATION FOR RE-USE IN THE LANDSCAPING. CONTINUE SLASHING AND RAKING LOTS AND PARK AREAS AS NECESSARY AND AS INSTRUCTED BY THE SUPERINTENDENT DURING THE CONTRACT AND MAINTENANCE PERIOD TO KEEP GRASS TO A MAXIMUM 50mm TO 100mm HIGH.
- ALL GULLIES AND DEPRESSIONS REQUIRING FILLING SHALL BE CLEARED, GRUBBED AND CLEANED OUT OF SILT, BOULDERS, DEBRIS ETC TO PROVIDE A CLEAN, FIRM BASE PRIOR TO PLACING ANY FILL OR FILTER MATERIALS. COMPACT ALL NATURAL SUBGRADES WITH 6 TO 8 PASSES OF A 10 TONNE VIBRATING ROLLER PRIOR TO PLACING ANY FILL MATERIALS. PLACE SUBSOIL DRAINS/MATS TO ENGINEERS APPROVALS AT THE BASE OF ALL SUCH FILLS AND OUTLET TO THE STORMWATER DRAINAGE SYSTEM. NOTIFY THE SUPERINTENDENT FOR AN INSPECTION PRIOR TO PLACING ANY FILL MATERIALS.
- 6. WHERE FILL IS PLACED ON SLOPING EXISTING SURFACE, THE EXISTING SURFACE SHALL BE BENCHED AND THE BENCH COMPACTED TO 98% SRDD PRIOR TO PLACING THE FILL MATERIAL.
- 7. ALL FILL GREATER THAN 400mm IS TO BE COMPLETED UNDER LEVEL 1 SUPERVISION
- 8. REMOVE SURFACE ROCKS FROM THE LOTS, FOOTPATHS, VERGES AND PARKLAND AREAS. REUSE IN SCOUR PROTECTION. REMOVE EXCESS FROM SITE OR STOCKPILE AS DIRECTED. ALL COSTS TO BE INCLUDED IN CONTRACT LUMP SUM.
- THE CONTRACTOR SHALL ENSURE NO PONDING AREAS RESULT FROM THE EARTHWORKS OPERATION.
   ANY SUCH AREAS WHICH DEVELOP SHALL BE RECTIFIED AS DIRECTED BY THE SUPERINTENDENT. THE CONTRACTOR SHALL NOTIFY THE SUPERINTENDENT OF THE DEVELOPMENT OR EXISTENCE OF ANY SUCH
- 10. BATTERS IN EXCESS OF BOTH 1.5m AND 1:2 SLOPE HIGH SHALL BE ASSESSED AND REPORTED FOR STABILITY (DURING CONSTRUCTION) BY A GEOTECHNICAL ENGINEER. COPIES OF REPORTS SHALL BE FORWARDED TO THE SUPERINTENDENT AND TO COUNCIL.
- 11. THE CONTRACTOR SHALL CONSTRUCT TEMPORARY BERMS AT THE TOP OF ALL BATTERS TO DIRECT AND CONTROL RUNOFF TO A SINGLE LOCATION. THE DISCHARGE OVER THE BATTER SHALL BE THROUGH A STABILISED CHUTE ADDRESSED IN THE CONTRACTORS PLAN, e.g. REINFORCED TURF, GEOTEXTILE, CONCRETE OR SIMILAR.
- 12. THE CONTRACTOR SHALL SET OUT (BY REGISTERED SURVEYOR) THE LOCATION OF ALL CUT BATTERS PRIOR TO COMMENCING THESE EARTHWORKS. HE SHALL ENGAGE A GEOTECHNICAL ENGINEER TO INSPECT, REPORT AND CHECK THE DESIGN PROFILE AND THE INSTITU MATERIAL FOR LONG TERM STABILITY, DESIGN AMENDMENTS AND ANY RETAINING WALLS SHALL BE FINALIZED TO COUNCIL'S APPROVALS PRIOR TO COMMENCEMENT OF ANY OF THESE EARTHWORKS.
- 13. ALL BOUNDARIES WITH EXISTING CREEKS AND VEGETATION MUST BE TEMPORARILY DELINEATED AND FENCED OFF/SEGREGATED TO RESTRICT BUILDING ACCESS FOR THE DURATION OF THE CONSTRUCTION
- 14. THE CONTRACTOR SHALL ENSURE THE PROPOSED CONSTRUCTION EQUIPMENT TO BE USED ON THE SITE WILL NOT DAMAGE EXISTING UNDERGROUND INFRASTRUCTURE, IN PARTICULAR HEAVY EQUIPMENT TRAVERSING OVER A.C. MAINS WITH NOMINAL COVERS.

### WATER RETICULATION NOTES

- VALVES AND HYDRANTS MUST BE LOCATED OPPOSITE BOUNDARY JUNCTIONS AND TRUNCATIONS.
- 2. WATER SUPPLY FITTINGS ARE TO INCORPORATE SOCKETS WITH AN EFFECTIVE SEALING LENGTH EQUAL OR GREATER THAN THAT OF THE UPVC PIPE USED.
- ALIGNMENT OF WATER RETICULATION MAINS WITHIN ROAD RESERVES TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CAIRNS REGIONAL COUNCIL.
- INSTALLATION OF VALVES AND FIRE HYDRANTS TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE CAIRNS REGIONAL COUNCIL.
- 5. ALL WORKS AND MATERIALS SHALL BE IN ACCORDANCE WITH FNQROC
- FOR DETAILS FOR KERB AND PAVEMENT MARKINGS AND RETROREFLECTIVE MARKERS AT HYDRANTS REFER TO FNOROC STANDARD DRAWINGS S2005 AND S2010.
- 7. THE CONTRACTOR SHALL MAKE ALL APPLICATIONS AND PAL ALL FEES TO COUNCIL FOR THE WATER SUPPLY WORKS AND HALL ARRANGE AND MANAGE COUNCILS INSPECTIONS AND TESTING OF THE WORKS. A COPY OF THE COUNCILS INSPECTIONS CERTIFICATE SHALL BE PROVIDED BY THE CONTRACTOR TO THE SUPER PRIOR TO PRACTICAL COMPLETION.
- 8. PROVIDE A COMPRESSIBLE LAYER BETWEEN ALL EXISTING AND PROPOSED HYDRANT OR VALVE SURROUNDS WITHIN AREAS OF NEW CONCRETE.

### ENVIRONMENTAL PROTECTION AND EROSION SEDIMENT CONTROL

- THE CONTRACTOR IS RESPONSIBLE WITHIN THE LIMITS IMPOSED BY THE WORKS, TO PROTECT AND PRESERVE THE NATURAL ENVIRONMENT AND AVOID POLLUTION.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INCORPORATION OF APPROPRIATE CONTROL MEASURES CONFORMING WITH THE REQUIREMENTS OF THE RELEVENT AUTHORITY.

### EROSION SEDIMENT CONTROL STRATEGY AND ENVIRONMENTAL PROTECTION

- THE CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT AND PRESERVE THE NATURAL ENVIRONMENT AND SHALL AVOID ENVIRONMENTAL POLLUTION IN ACCORDANCE WITH THE ENVIRONMENTAL PROTECTION ACT.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INCORPORATION OF APPROPRIATE CONTROL AND MANAGEMENT MEASURES CONFORMING TO THE REQUIREMENTS OF THE ACT AND THE RELEVANT AUTHORITIES.
- 3. THE EROSION AND SEDIMENT CONTROL STRATEGY, SHOWN OR NOTED ON THESE DRAWINGS, HAS BEEN PROVIDED AS A GUIDE.
- 4. THE CONTRACTOR SHALL PROVIDE AN EROSION SEDIMENT CONTROL PLAN (ESCP) FOR EACH PHASE OF HIS PROPOSED CONSTRUCTION PROGRAM AND WORK METHODS, AND IS WHOLLY RESPONSIBLE FOR THE IMPLEMENTATION, CONTROL AND MANAGEMENT OF SUCH PLAN.
- THE CONTRACTOR SHALL INSTALL ALL DEVICES/MEASURES NECESSARY TO COMPLY WITH THE PROVISIONS OF THE ESCP FNORCO DEVELOPMENT MANUAL, THE ENVIRONMENTAL PROTECTION ACT, AND COUNCIL REQUIREMENTS.
- 6. THE ESCP SHALL INCLUDE SUCH MEASURES AS SHOWN ON THE STRATEGIC PLAN.
- 7. PDR ENGINEERS DO NOT ACCEPT RESPONSIBILITY FOR THE CONTRACTOR'S DESIGN & IMPLEMENTATION OF HIS ESCP NOR THE CONSEQUENCES OF HIS FAILURE TO APPLY ALL REASONABLE CONTROLS.
- 8. ALL STORMWATER INLETS, TRENCHES, ETC, SHALL BE CONSTRUCTED IN SUCH A WAY AS TO PREVENT THE ENTRY OF SEDIMENT INTO THE STRUCTURE. IF IT IS NECESSARY TO DISCHARGE INTO SUCH INLETS THEN SUITABLE SILT TRAPS SHALL BE CONSTRUCTED UPSTREAM OF THE INLETS SUCH THAT OVERFLOW FROM TRAPS ENTERS THE DRAINS AFTER THE SEDIMENT HAS DROPPED OUT.
- ALL SEDIMENT CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL THE END OF THE MAINTENANCE PERIOD, UNLESS NOTED OTHERWISE. ALL SEDIMENT CONTROL DEVICES ARE TO BE FULLY MAINTAINED IN AN EFFECTIVE WORKING CONDITION DURING CONSTRUCTION AND THE MAINTENANCE PERIOD. THE CONTRACTOR SHALL ENSURE THAT ALL SEDIMENT CONTROL DEVICES ARE KEPT FREE OF SEDIMENT
- 10. SEDIMENT FENCES SHALL BE INSTALLED SUCH THAT THE BASE OF THE FENCE IS PLACED 150MM MINIMUM BELOW GROUND LEVEL, AND ANCHORED SECURELY IN SUCH POSITION.
- ALL VEHICLE EXIT POINTS SHALL HAVE SHAKER GRIDS, WASH BAYS OR SIMILAR TO PREVENT VEHICLES FROM TRACKING SOIL AND MUD OFF SITE.
- 12. ALL SOIL STOCKPILES SHALL BE PROTECTED AGAINST WIND EROSION BY COVERING AND AGAINST STORMWATER RUNOFF BY SILT FENCES AT THE DOWNHILL SLOPES. STOCKPILE LOCATIONS SHALL BE DETERMINED BY THE CONTRACTOR AND EROSION/CONTROL MEASURES IMPLEMENTED & MAINTAINED FOR THE STOCKPILE.
- 13. THE CONTRACTOR SHALL INSTALL TURF STRIPS BEHIND ALL KERB & CHANNEL, ADJACENT CONCRETE INVERTS AND ALLOTMENT DRAINS ETC WHERE DIRTY WATER SHEET FLOWS INTO DRAINAGE COLLECTION
- 14. DIVERT CLEAN WATER AROUND AREAS OF CONSTRUCTION.
- 15. DRILL SEED ALL ROAD SHOULDERS, FOOTPATHS, DRAINS AND CUT BATTERS UP TO 1 on 2 SLOPE WITH APPROVED GRASS SPECIES, FERTILIZED AND MAINTAIN FOR THE REQUIRED MAINTENANCE PERIOD
- 16. HYDROMULCH ALL CUT AND FILL BATTERS STEEPER THAN 1 on 2, WITH APPROVED SUITABLE GRASS SPECIES AND MAINTAIN FOR THE REQUIRED MAINTENANCE PERIOD
- 17. THE CONTRACTOR SHALL CONSTRUCT TEMPORARY BERMS AT THE TOP OF ALL BATTERS TO DIRECT AND CONTROL RUNOFF TO A SINGLE LOCATION. THE DISCHARGE OVER THE Batter SHALL BE THROUGH A STABILIZED CHUTE ADDRESSED IN THE CONTRACTORS PLAN, e.g. REINFORCED TURF, GEOTEXTILE, CONCRETE OR SIMILAR.
- 18. ALL WORKS AND MATERIALS SHALL BE IN ACCORDANCE WITH FNQROU

TITLEBLOCK REVISED A FOR COUNCIL SUBMISSION 15.02.16 DESCRIPTION DATE

**FOR** CONSTRUCTION

rawing Status

SCALE N/A Α1 DO NOT SCALE DRAWINGS cales Before Reduction


JACOBS


WALKER ROAD PTY LTD


**CHERRYBROOK** STAGES 2 AND 3 Drawing Title

DRAWING SET NOTES


Designed PAM RJB RJC JUN 2017 15495 - C202







FOR EARTHWORKS, SUBGRADE AND FILL NOTES REFER TO DRG 15495-C202.



TYPICAL SECTION - INTERFACE BATTER DETAILS

N.T.S.

Drawing Title


ļ				Drawing State
l				
I	D	TITLEBLOCK REVISED	08.06.17	
I	C	EARTHWORKS REVISED	26.05.17	
Ì	В	TEMPORARY DRAIN AMMEDED - Q100 SWALE AMMENDED	12.05.16	
l	Α	FOR COUNCIL SUBMISSION	15.02.16	CONS
Į	ISSUE	DESCRIPTION	DATE	

FOR CONSTRUCTION




WALKER ROAD PTY LTD CHERRYBROOK STAGES 2 AND 3 EARTHWORKS PLAN SHEET 2 OF 2


Drawn	Designed	٧	erified/		
JP	PAM	R	:JB		
Approved RJC			Date JUN 2017		
Drawing Nun			Revision D		



# 503 501 Stage 3 05 306 308 307 309 \_ E\_ $\Xi$ 140 .000 375mm RCP ROAD 02 — 3.0m WIDE CONCRETE HARDSTAND REFER FNQROC STD. DRG. S1110 FOR DETAILS. ACCESS CROSS OVER. BEFER ENGROC STD DRG S1015 FOR DETAILS. PRE CAST CONCRETE HEADWALL TO SUIT 450 RCP OUTLET 302 303 304 - GROUTED STONE PITCHING (10.0m<sup>2</sup> NOMINAL) - 3.0m WIDE EXPOSED AGGREGATE "OCEAN FLOOR" CONCRETE DRIVEWAY REFER FNOROC STD. DRG. S1110 FOR DETAILS. 102 101 PLAN 1:250

### LEGEND





FOR ROADWORKS NOTES REFER TO DRG 15495-C202.

### CONTROL LINE ROAD 01 SETOUT


CHAINAGE	COORD	INATES	BEARING	RADIUS OF	TANGENT	ARC
	EASTING	NORTHING	DEG MIN SEC	CURVATURE	LENGTH	LENGTH
0.000	363357.825	8118956.291	267* 45' 35"	STRAIGHT		
18.166	363339.673	8118955.581	267? 45' 35"	30.000		
IP 29.359	363327.939	8118955.122	-	30.000	11.743	22.386
40.553	363319.011	8118962.750	310? 30' 51"	STRAIGHT		
133.786	363248.131	8119023.318	310? 30' 51"	-300.000		
IP 144.847	363239.718	8119030.507	-	-300.000	11.066	22.122
155.908	363230.798	8119037.057	306? 17' 21"	STRAIGHT		
231.082	363170.205	8119081.549	306? 17' 21"	100.000		
IP 234.969	363167.070	8119083.851	-	100.000	3.889	7.774
238.856	363164.124	8119086.389	310? 44' 35"	-99.998		
IP 242.735	363161.183	8119088.922	-	-99.998	3.881	7.759
246.615	363158.055	8119091.220	306? 17' 51"	STRAIGHT		
360.526	363066.248	8119158.653	306? 17' 51"	-100.000		
IP 365.813	363061.982	8119161.786	-	-100.000	5.292	10.574
371.101	363057.410	8119164.451	300? 14' 20"	100.000		
IP 376.388	363052.838	8119167.116	-	100.000	5.292	10.574
381.675	363048.573	8119170.249	306? 17' 51"	STRAIGHT		
469.584	362977.722	8119222.289	306° 17′ 51"	100.000		
IP 474.850	362973.474	8119225.409	-	100.000	5.271	10.532
480.116	362969.578	8119228.959	312* 19' 54"	-100.000		
IP 485.396	362965.671	8119232.518	-	-100.000	5.285	10.561
490.677	362961.410	8119235.646	306* 16' 51"	STRAIGHT		
539.449	362922.094	8119264.506	306° 16′ 51"	-30.000		
IP 544.876	362917.670	8119267.753	-	-30.000	5.488	10.855
550.304	362912.383	8119269.225	285* 32' 57"	STRAIGHT		
557.145	362905.793	8119271.058	285* 32' 57"	STRAIGHT		

# CONTROL LINE ROAD 02 SETOUT

CHAINAGE	COORDINATES		BEARING	RADIUS OF	TANGENT	ARC
	EASTING	NORTHING	DEG MIN SEC	CURVATURE	LENGTH	LENGTH
0.000	363270.960	8119003.810	36* 16' 51"	STRAIGHT		
140.891	363354.331	8119117.386	36* 16' 51"	20.000		
IP 145.108	363356.864	8119120.837	-	20.000	4.281	8.434
149.325	363360.588	8119122.948	60° 26′ 35″	STRAIGHT		
162.756	363372.272	8119129.574	60° 26′ 35″	STRAIGHT		

### STORMWATER SETOUT

- HEADWALL SETOUT POINTS TO CENTRE OF PIPE OUTLET.
  SETOUT OF GROSS POLLUTANT TRAP IS TO CENTRE OF THE PIT
  REFER DETAIL THIS DRAWING FOR KERB INLET PIT SETOUT DETAILS.



# GRATED KERB INLET PIT SETOUT REFERENCE POINT

E	BUILD TO BOUNDARY LINE SHOWN	22.06.17	П
D	TITLEBLOCK REVISED	08.06.17	П
С	DRAINAGE REVISED	26.05.17	П
В	EARTHWORKS AMMEDED	12.05.16	П
Α	FOR COUNCIL SUBMISSION	15.02.16	П
ISSUE	DESCRIPTION	DATE	П

Drawing Status FOR CONSTRUCTION

Orig. Shee SCALE 1:250 A1 DO NOT SCALE DRAWINGS


**JACOBS** 

WALKER ROAD PTY LTD

CHERRYBROOK STAGES 2 AND 3

Prawing Title **ROAD WORKS AND DRAINAGE** PLAN SHEET 2 OF 2

	Drawn	Designed	V	'erified
_	JP	PAM	R	JB
Е	Approved	•	С	ate
	RJC		J	UN 2017
	Drawing Number			Revision
	15495 -	C206		E)



HORIZONTAL SCALE 1:500 5 0 5 10 15 20 25 VERTICAL SCALE 1:50 0 5 0 0.5 1 1.5 2.0 2.5

L	$\vdash$		
ı			
ı			
ı	C	TITLEBLOCK REVISED	08.06.17
ı	В	LONGITUDINAL SECTIONS REVISED	26.05.17
ı	Α	FOR COUNCIL SUBMISSION	15.09.16
ı	ISSUE	DESCRIPTION	DATE


FOR CONSTRUCTION


Drawing Status


SCALE N/A Orig. Sheet
A1
DO NOT SCALE DRAWINGS
Scales Before Reduction




WALKER ROAD PTY LTD CHERRYBROOK STAGES 2 AND 3 BENTLEY DRIVE LONGITUDINAL SECTION










D	TITLEBLOCK REVISED	08.06.17
C	CROSS SECTIONS REVISED	26.05.17
В	225 DIA WATER MAIN ADDED TO SECTIONS CH130-141.62	12.05.16
Α	FOR PRELIMINARY REVIEW	15.02.16
ISSUE	DESCRIPTION	DATE

Drawing Status FOR CONSTRUCTION






CHERRYBROOK STAGES 2 AND 3

BENTLEY DRIVE CROSS SECTIONS

Drawing Title

Drawn	Designed	٧	erified
JP	PAM	R	ЈВ
Approved			ate
RJC		J	UN 2017
Drawing Number			Revision
- (/+ני	C2V0		ر تا

5	WALKER ROAD
-61 7 4031 4599	PTY LTD



LONGITUDINAL SECTION ROAD 02

HORIZONTAL SCALE 1:500 5 0 5 10 15 20 25

VERTICAL SCALE 1:50 0.5 0 0.5 1 1.5 2.0 2.5

C	TITLEBLOCK REVISED	08.06.17
В	LONGITUDINAL SECTION REVISED	26.05.17
Α	FOR COUNCIL SUBMISSION	15.02.16
ISSUE	DESCRIPTION	DATE


FOR CONSTRUCTION

SCALE N/A	Orig. Sheet			
SCALE N/A	A1			
DO NOT SCALE DRAWINGS				
Scales Before Reduction				
·				

JACO	<b>BS</b>
ABN 37 001 024 095 and ACN 001 024 095 Jacobs Group (Australia) Pty Ltd	
2 James Street	Tel: +61 7 4031 4599
CAIRNS, QLD 4870	Fax: +61 7 4031 3967
AUSTRALIA	Web: www.jacobs.com

WALKER ROAD PTY LTD CHERRYBROOK STAGES 2 AND 3 ROAD 02
LONGITUDINAL SECTION

Drawn JP	Designed PAM		erified JB		
Approved RJC			Date JUN 2017		
Drawing Number 15495 - C209			Revision		



C	TITLEBLOCK REVISED	08.06.1
В	CROSS SECTIONS REVISED	26.05.1
Α	FOR COUNCIL SUBMISSION	15.02.10
ISSUE	DESCRIPTION	DATE

FOR CONSTRUCTION

SCALE 1:100				Jilg. c	nieet	Ш	
SCALE 1.100				Α	A1		
DO NOT SCALE DRAWINGS							
ales Before Reduction							
1 0	1	2	3	4	5	m	
							. –

JACOBS

N37 001 024 095 and ACN 001 024 095 dots Group (Justralia) Ply Ltd


Tel:-461 7 4031 4599


Fax:-461 7 4031 3997

Fax:-461 7 4031 3997

WALKER ROAD PTY LTD CHERRYBROOK STAGES 2 AND 3 ROAD 02 CROSS SECT

	Diawii	Designed	v	enneu
	JP	PAM	R	JB
ROAD 02	Approved RJC			ate UN 20
SS SECTIONS	Drawing Nun	nber C210		Revisio





	EXISTING PROPERTY BOUNDARIES
	EXISTING SURFACE CONTOURS
	EXISTING BATTER CHANGE IN GR
	EXISTING ROAD CROWN
	EXISTING KERBING
	NEW BATTER
24.0	DESIGN SURFACE CONTOURS
	NEW ROAD CROWN
	NEW LAYBACK KERB AND CHANN
0 =	NEW KERB INLET PIT
	NEW DRAINAGE PIPE AND SIZE
	PROPOSED LOT BOUNDARIES
	FUTURE LOT BOUNDARIES
	CATCMENT BOUNDARY
ightharpoonup	OVERLAND FLOW

D	TITLEBLOCK REVISED	08.06.17
Ċ	CATCHMENT BOUNDARIES REVISED	26.05.17
В	ULTIMATE CATCHMENT INFORMATION ADDED	12.05.16
Α	FOR PRELIMINARY REVIEW	15.02.16
ISSUE	DESCRIPTION	DATE

FOR CONSTRUCTION

 SCALE 1:500
 Orig. Sheet A1

 DO NOT SCALE DRAWINGS

 cales Before Reduction

 5
 0
 5
 10
 15
 20
 25
 m


JACOBS\*

ABN 37 001 024 005 and ACN 001 024 005
Lacobs Group (Australia) Phy Ltd

Tel: 461 7 4/031 4500

WALKER ROAD PTY LTD CHERRYBROOK STAGES 2 AND 3 DRAINAGE CATCHMENT PLA

	Drawn JP	Designed PAM	Verified RJB		
.AN	Approved RJC		Date JUN 2017		
	Drawing Nun				vision D




	LOCATION		SUB-CA	TCHMENT	r runoff	F						INI	LET DESIG	6N						DRAIN DESIGN HEAD LOSSES PART FULL									DESIGN LEVELS																		
		Тс	1	Α	CA	Qc	Qa									Qg C	Qb	Тс	1	CA	Qraf	: Q	L	S			Vf=Q/A	Qcap	Vcap	Vt		Vf²/2g	Ku	hu	Kw	hw	Sf	hf	dn	Vn							
STRUCTURE No.	DRAIN SECTION	SUB-CATCHMENT TIME OF CONC.	RAINFALL INTENSITY	SUB-CATCHMENT AREA	EQUIVALENT AREA	SUB-CATCHMENT DISCHARGE	FLOW IN K&C (INC. BYPASS)	HALF ROAD CAPACITY	FLOW WIDTH	FLOW DEРТН	FLOW DxV	ROAD GRADE AT INLET	ROAD XFALL AT INLET	INLET TYPE	INLET CURVE	FLOW INTO INLET	BYPASS STRUCTURE No.	CRITICAL TIME OF CONC.	RAINFALLINTENSITY	TOTAL (C x A)	PEAK FLOW	PIPE FLOW	REACH LENGTH	PIPE GRADE	PIPESIZE	PIPE CLASS	FULL PIPE VELOCITY	CAPACITY FLOW	CAPACITY VELOCITY	TRAVEL VELOCITY	CHART(S) USED	VELOCITY HEAD	U/S HEAD LOSS COEFFICIENT	U/S HEAD LOSS	W.S.E COEFFICIENT	CHANGE IN W.S.E	PIPE FRICTION SLOPE	PIPE FRICTION HEAD LOSS	NORMAL DEPTH	NORMAL DEPTH VEL.	PIPE U/S I.L	PIPE D/S I.L	PIPE U/S H.G.L	PIPE D/S H.G.L	W.S.E	GRATE LEVEL	STRUCTURE No.
		min	mm/h	ha	ha	L/s	L/s	L/s	m	m	m^2/s	s %	%			L/s L	/s	min	mm/h	r ha	L/s	L/s	m	%	mm		m/s	L/s	m/s	m/s		m		m		m	%	m	m	m/s	m	m	m	m	m	m	
12/1	12/1 to 11/1	10.00	128	0.078	0.056	20	20	897	1.199	0.045	0.041	3.85	3.00	KIP-OG-S	2% - 6%	17 3	6/13	11.22	123	1.480	506	513	83.824	3.79	525	RCP (2)	2.37	838	3.87	2.00	T1/T2	0.287	0.41	0.119		0.119	.40	2.854	0.297 4	1.06	57.841	54.662	58.366	55.512	58.485	59.726	12/1
11/1	11/1 to 10/1	10.00	128	0.056	0.040	14	14	758	0.847	0.050	0.044	3.53	3.00	KIP-OG-S	2% - 6%	12 2	1/14	11.42	122	1.943	660	671	80.471	2.70	525	RCP (2)	3.10	707	3.27	2.00	T1/T2	0.491	0.32	0.158	-	0.158	.43	1.959	0.408	3.72	54.642	52.468	55.354	53.394	55.512	56.501	11/1
10/1	10/1 to 9/1	10.00	128	0.060	0.043	15	15	806	1.115	0.042	0.034	3.27	2.99	KIP-OG-S	2% - 6%	13 2	5/7	12.09	120	1.986	660	669	12.486	3.06	600	RCP (2)	2.37	1074	3.80	2.00	T4/T8	0.285	0.82	0.234	0.98	0.280	.19	0.148	0.343 4	.00	52.393	52.012	53.160	53.012	53.440	54.051	10/1
9/1	9/1 to 8/1	10.00	128	0.416	0.299	106	106	883	2.345	0.077	0.103	3.74	3.00	KIP-OG-S	2% - 6%	77 30	8/1	12.20	119	2.285	757	736	58.794	5.43	600	RCP (2)	2.60	1431	5.06	2.00	T4/T8	0.345	1.22	0.420	1.27	0.438	.08	2.987	0.305	.10	51.992	48.800	52.592	49.605	53.029	53.783	9/1
8/1	8/1 to 7/1	10.00	128	0.213	0.153	55	85	1488	1.943	0.066	0.101	6.20	3.00	KIP-OG-S	2% - 6%	63 21	. 7/1	12.69	117	2.439	794	782	24.060	3.62	600	RCP (2)	2.77	1169	4.14	2.00	T1/T2	0.390	0.60	0.233	- 0	0.233	.62	0.502	0.359 4	1.43	48.772	47.900	49.372	48.259	49.605	50.454	8/1
7/1	7/1 to 6/1	10.00	128	0.030	0.021	8	29	1401	1.325	0.048	0.053	5.31	3.09	KIP-OG-S	2% - 6%	24 5	6/1	12.89	116	2.460	796	800	13.215	5.50	750	RCP (2)	1.81	2612	5.91	2.00	T8	0.167	1.02	0.171	1.61	0.270 4	.63	0.611	0.285	5.20	47.110	46.383	47.860	47.249	48.130	49.078	7/1
6/1	6/1 to 5/1	10.00	128	0.030	0.022	8	12	223		0.000		0.82	3.03	KIP-SAG-S	SAG S	12 0	3/1	12.86	117	2.782	901	910	4.654	1.25	900	RCP (2)	1.43	2025	3.18	2.00	T4/T8	0.104	1.41	0.147	1.50	0.157	.25	0.012	0.423	3.10	46.139	46.081	47.101	47.090	47.258	48.588	6/1
5/1	5/1 to 4/1	1												GPT-CA750				12.89	116	2.782	900	909	2.891	1.25	900	RCP (2)	1.43	2025	3.18	2.00	T1	0.104	0.20	0.021	-	0.021	.25	0.007	0.423	3.10	46.061	46.024	47.069	47.061	47.090	48.856	5/1
4/1	4/1 to 3/1	1												мн				13.06	116	2.795	899	908	10.512	1.45	900	RCP (2)	1.43	2184	3.43	2.00	T8	0.104	1.51	0.157	1.60	0.166	.12	0.118	0.405	3.27	46.004	45.852	46.904	46.787	47.071	48.904	4/1
3/1	3/1 to 2/1	10.00	128	0.145	0.104	37	37	294		0.009		0.41		KIP-SAG-S	SAG S	37 0	2/1	13.15	116	2.899	931	939	16.958	2.00	900	RCP (2)	1.48	2561	4.03	2.00	T2/T4	0.111	0.50	0.055	- 1	0.055	.65	0.280	0.377	3.71	45.832	45.492	46.732	46.452	46.787	48.674	3/1
2/1	2/1 to 1/1		128	0.233	0.167	60	60	300		0.020		0.60		KIP-SAG-S	SAG S	60 0	2/x1	13.29	115	3.066	981	990	11.621	2.00	900	RCP (2)	1.56	2571	4.04	2.00	T2/T4	0.123	0.64	0.079	- 1	0.079	.40	0.144	0.388	3.77	45.472	45.240	46.372	45.628	46.452	48.674	2/1
1/1	77-													HW			-,									(-/																				46.140	1/1
6/7	6/7 to 5/7	10.00	128	0.234	0.168	60	60	71	2.765	0.089	0.049	0.50	3.00	KIP-OG-S	1%	48 12	1/9	10.00	128	0.168	60	48	7.085	0.40	375	RCP (2)	0.44	111	1.00	2.00	G2	0.010	8.61	0.083	- 1	0.083	.08	0.005	0.173	0.97	51.960	51.932	52.515	52.510	1	53.013	6/7
5/7	5/7 to 4/7	10.00	128	0.252		65	67	70			0.052			KIP-OG-S	1%	53 14	4/7	10.06		0.350				0.71	1	RCP (2)	0.91	148			G1/T4/T8	0.042			2.55		.33	0.240	0.227 1		51.912	51.394	52,406	52.167		52.990	5/7
4/7	4/7 to 3/7	10.00	128		0.189	67	82	84			0.051	0.50		KIP-OG-S	1%	62 20	3/7	10.61		0.672			27.529	0.80	450	RCP (2)	1.29	255			T4/T8	0.085		0.145		0.153	.52		0.306 1	.78	51.319	51.098	52.022	51.879	52.175	52.624	4/7
3/7	3/7 to 2/7	10.00				60	92	276	0.775	0.037	0.001	0.16		KIP-SAG-S	SAG S	92 0	2/x3	10.84		0.842			7.724			RCP (2)	1.85	403	1	2.00	T1	0.174		0.235		- 1	.06			2.77		50.924	51.644	51.562	51.879	52.448	3/7
2/7	2/7 to 1/7	10.00	120	0.230	0.170		-	2,0		0.037		0.10		GPT-CA375	57103		2,73	10.90		0.842			l				1.84			2.00		0.174		0.208		0.208						1	51.354	50.985		52.846	2/7
1/7	2// (0 1//	1												HW/				10.50	124	0.042	251	255	10.155	2.00	130	(Z)	1.04	403	2.55	2.00		0.174	1.20	0.200		200	.02	0.155	0.203		30.304	30.700	31.334	30.303	50.985	51.150	1/7
1/9	1/9 to 4/7	10.00	128	0.186	0.134	48	59	72	3.070	0.085	0.045	0.41	2.73	KIP-OG-S	1%	48 12	3/7	10.00	128	0.134	48	48	7.561	0.50	375	RCP (2)	0.43	124	1.12	2.00	62	0.010	6.41	0.061	١,	0.061	.07	0.006	0.162 1	.05	51.431	51.394	52.172	52.167	52.234	52.648	1/9
3/10	3/10 to 2/10	1	128		0.115	41	147	1		0.061	0.068	3.65		KIP-OG-S	2% - 6%	40 8	2/10	10.00		0.134					1	RCP (2)	0.36	248	2.25	2.00	G2	0.010		0.064			.05					55.677	56.439	56.432	56.503	57.808	3/10
2/10	2/10 to 1/10	1	128	0.281	0.203	72	80	270	1.014	0.001	3.000	1.34		KIP-SAG-S	SAG S	80 0	1/10	10.00	128	0.113		119	7.500	0.40	375	RCP (2)	1.08	111	1.00		G2/T4/T8	0.059		0.212			.46		0.375	08	55.657	55.627	56.220	56.186	56.433	57.008	2/10
1/10	1/10 to 11/1	1				47	47	115		0.014		1.34		KIP-SAG-S	SAGS	47 0	9/1	10.06	128	0.449		166	26.377	3.09	375	RCD (2)	1.50	308		2.00	1 1 1			0.212						2.84		1		55.512	56.193	57.008	1/10

CALCULATIONS TABLE

D	TITLEBLOCK REVISED	08.06.17
С	TABLE REVISED	26.05.17
В	FLOW THROUGH 10/1 ADDED	12.05.16
Α	FOR PRELIMINARY REVIEW	15.02.16
ISSUE	DESCRIPTION	DATE

FOR CONSTRUCTION






WALKER ROAD PTY LTD CHERRYBROOK STAGES 2 AND 3 DRAINAGE CALCULATION TABLES

Drawing Title

					ı
	Drawn	Designed	٧	erified	I
	JP	PAM	R	ЈВ	I
ATION	Approved		С	ate	I
	RJC		J	UN 2017	I
	Drawing Nun	nber		Revision	١
	15495 -	C214		D	J



EXISTING PROPERTY BOUNDARIES

24.0 EXISTING SURFACE CONTOURS
EXISTING ROAD CROWN
EXISTING ROAD CROWN
EXISTING KERBING

NEW BATTER - TOE
DESIGN SURFACE CONTOURS

NEW ROAD CROWN
NEW LAYBACK KERB AND CHANNEL

NEW STORMWATER STRUCTURES - MH AND KERB
INLET PIT
PROPOSED LOT BOUNDARIES
FUTURE LOT BOUNDARIES
SAND BAGS AROUND STORMWATER INLETS

SILT FENCE
TEMPORARY CUT DRAINAGE PATH


ROCK CHECK DAMS ALONG TEMPORARY DRAINAGE PATH

SAND BAGS ALLONG KERBS

THIS DRAWING IS SUPERSEDED BY JACOBS DRAWING IH035500-CI-DG-0413 TO 0415 ON THE BASIS THAT STAGES 2, 3 & 4 WILL BE CONSTRUCTED CONCURRENTLY.

			Drawing S
D	TITLEBLOCK REVISED	08.06.17	
C	PLAN SUPERSEDED BY DRGS	26.05.17	
В	EARTHWORKS AMMEDMENTS	12.05.16	
А	FOR PRELIMINARY REVIEW	15.02.16	CO
ICCIIE	DESCRIPTION	DATE	l

FOR CONSTRUCTION








WALKER ROAD PTY LTD CHERRYBROOK STAGES 2 AND 3 EROSION AND SEDIMENT CONTROL PLAN

Drawing Title

Drawn JP	Designed PAM	erified JB
Approved RJC		oate UN 2017
Drawing Nun		Revision D







HCBS CLOSEST TO PROPERTY BOUNDARY ARE SET AT 1m OFFSET TO BOUNDARY. HCBS UPSTREAM OF HCBS CLOSEST TO THE PROPERTY BOUNDARY ARE OFFSET 0.5m TO DOWNSTREAM HCB.

		110
E	BUILD TO BOUNDARY LINE SHOWN 22.06.17	11
D	TITLEBLOCK REVISED 08.06.17	11
С	SEWERAGE REVISED 26.05.17	11
В	SEWER LINE 4 SETOUT AMMENDED 12.05.16	11
Α	FOR PRELIMINARY REVIEW 15.02.16	11
ICCUE	DESCRIPTION	٦١.

FOR CONSTRUCTION

SCALE 1:250 Orig. Sheet
A1
DO NOT SCALE DRAWINGS
Scales Before Reduction
25 0 2,5 5 7,5 10 12.5 m





WALKER ROAD PTY LTD CHERRYBROOK


STAGES 2 AND 3

Drawing Title

SEWERAGE PLAN SHEET 2 OF 2 Drawn Designed Verified JP PAM RJB
Approved Date RJC JUN 2017
Drawing Number Revision 15495 - C217 E








E	LINEMARKING REVISED, BUILD TO BOUNDARY LINE SHOWN	22.06.17
D	TITLEBLOCK REVISED	08.06.17
С	WATER AND LINEMARKING REVISED	26.05.17
В	LINEMARKING PLAN ADDED, WATER FIXTURE AMMENDMENTS	12.05.16
Α	FOR PRELIMINARY REVIEW	15.02.16
ISSUE	DESCRIPTION	DATE

FOR CONSTRUCTION



JACOBS\*

ABN 37 001 024 095 and ACN 001 024 095
Jacobs Group (Australia) Pty Ltd

WALKER ROAD PTY LTD CHERRYBROOK STAGES 2 AND 3 WATER RETICULATION AND LINE MARKING PLAN

Prawing Title

Drawn	Designed	V	'erified
JP	PAM	R	JB
Approved		Г	ate
RJC		Į	UN 2017
Drawing Nur	nber		Revision
15495 -	C219		D